



<http://www.youtube.com/watch?v=QHDJtRX-NT8>

This specification is provided by Lythic Solutions as a service and is intended to be used as a guideline for preparing the appropriate project specific specification sections. Every heading may not be needed. Delete headings not used and renumber remaining used headings to be numerically correct.

HardWear Floor

PART 1 GENERAL

1.01 SUMMARY

- A. This section includes the following.
 - 1. Concrete Slab preparation for densifier application and burnished floor.
- B. Related Work:
 - 1. Section 03300 Cast-In-Place Concrete

1.02 REFERENCES

- A. American Society for Testing and Materials:
 - 1. ASTM-C501, Standard Test Method for Abrasion Resistance of Horizontal Concrete Surfaces
- B. American Concrete Institute
 - 1. ACI 302. 1R-89, Guide for Concrete Floor and Slab Construction
- C. Other Test:
 - 1. Reflectivity

1.03 SUBMITTALS

- A. Comply with pertinent provisions of Section 01600- Product Requirements:
 - 1. Provide submittal information within 35 calendar days after the contractor has received the owner's notice to proceed.
- B. Product data:
 - 1. Submit special concrete finishes manufacturer's specifications and test data.
 - 2. Submit special concrete finishes describing product to be provided, giving manufacturer's name and product name for the specified material proposed to be provided under this section.



3. Submit special concrete finishes manufacturer's recommended installation procedures; which when approved by the Architect, will become the basis for accepting or rejecting actual installation procedures used on the work.
 4. Submit special concrete finishes technical data sheet giving descriptive data, curing time, and application requirements.
 5. Submit special concrete finishes manufacturer's Material Safety Data Sheet (MSDS) and other safety requirements.
 6. Follow all special concrete finishes published manufacturer's installation instructions.
- C. Test Reports:
1. Provide certified test reports, prepared by an independent testing laboratory, confirming compliance with specified performance criteria.
- D. Samples:
1. Each floor has its own unique appearance when completed. Manufacturer's lab samples are supplied only to show a smooth reflective surface. The final appearance of the finished floor cannot be guaranteed to match a sample due to the natural variations in concrete.
- E. Product Variations:
1. The variegated colors produced are unique to each concrete surface and depend on the chemical composition, mix design, porosity, age, texture, and color of the concrete substrate. Mottling and wide variations in color and intensity may occur. If contaminants remain on the surface, the penetration of Lythic Densifier and Lythic XL Densifier may be blocked. Concrete from different loads or pours, and in patched in areas, may appear significantly different in color than adjacent areas.

1.04 QUALITY ASSURANCE

- A. Installer Qualifications:
1. Use a certified installer and adequate number of skilled workmen who are thoroughly trained and experienced in the necessary craft.
 2. The special concrete finish manufacturer shall certify applicator.
 3. Applicator shall be familiar with the specified requirements and the methods needed for proper performance of work of this section. Applicator must have availability of proper equipment to perform work within scope of this project on a timely basis. Applicator should have successfully performed a minimum of 5 projects of at least 5000 square feet each.



- B. Manufacturer's Certification:
 - 1. Provide letter of certification from concrete finish manufacturer stating that installer is certified applicator of special concrete finishes, and is familiar with proper procedures and installation requirements required by the manufacturer.

- C. Mock-ups:
 - 1. Apply mock-ups of each type finish, to demonstrate typical joints, surface finish, color variation (if any), and standard of workmanship.
 - a. Build mock-ups approximately 20 square feet in the location indicated or if not indicated, as directed by the Architect or Owner Representative.
 - b. Notify Architect or Owner Representative seven days in advance of dates and times when mock-ups will be constructed when practical.
 - c. Obtain from the Architect or Owner Representative approval of mock-ups before starting construction.
 - d. If the Architect or Owner Representative determines that mock-ups do not meet requirements, demolish and remove them from the site and cast others until mock-ups are approved.
 - e. Maintain mock-ups during construction in an undisturbed condition as a standard for judging the completed work.
 - f. Approved mock-ups may become part of the completed work if undisturbed at time of substantial completion.

- D. Protection
 - 1. No satisfactory chemical or cleaning procedure is available to remove petroleum stains from the concrete surface. Prevention is therefore essential.
 - a. All hydraulic powered equipment must be diapered to avoid staining of the concrete.
 - b. No trade will park vehicles on the inside slab. If necessary to complete their scope of work, drop cloths will be placed under vehicles at all times.
 - c. No pipe cutting machine will be used on the inside floor slab.
 - d. Steel will not be placed on interior slab to avoid rust staining.
 - e. All equipment must be equipped with non-marking tires.

- E. Pre-Installation Conference:
 - 1. Conduct conference at project site to comply with requirements in Division 1 Section "Project Management and Coordination"



1.05 DELIVERY, STORAGE AND HANDLING

- A. Deliver materials in original containers, with seals unbroken, bearing manufacturer labels indicating brand name and directions for storage.
- B. Dispense special concrete finish material from factory numbered and sealed containers. Maintain record of container numbers.

1.06 PROJECT CONDITIONS

- A. Environmental limitations:
 - 1. Comply with manufacturer's written instructions for substrate temperature and moisture content, ambient temperature and humidity, ventilation, and other conditions affecting topping performance.
 - a. Concrete must have a Floor Flatness rating of at least 40.
 - b. Concrete must have a Floor Levelness rating of at least 40.
 - c. Concrete must be cured a minimum of 28 days or as directed by the manufacturer before application of Lythic Densifier and Lythic XL Densifier can begin.
 - d. Application of Lythic Densifier/Lythic XL Densifier shall take place 10 days prior to installation of equipment and substantial completion, thus providing a complete, uninhibited concrete slab for application.
- B. Close areas to traffic during floor application and after application, for time period recommended in writing by manufacturer.



PART 2 – PRODUCTS

2.01 MATERIALS AND MANUFACTURERS

A. DENSIFYING AGENT

1. Lythic Densifier, manufactured by:
Lythic Solutions, Vancouver, WA
888-598-4421, 360-694-5347
2. Lythic XL Densifier, manufactured by:
Lythic Solutions, Vancouver, WA
888-598-4421, 360 694 5347
3. Lythic Protector, manufactured by:
Lythic Solutions, Vancouver, WA
888-598-4421, 360 694 5347

2.02 RELATED MATERIALS

- #### **A. Water:**
1. Potable

PART 3- EXECUTION

3.01 SURFACE CONDITIONS:

- A. Examine substrate, with installer present, for conditions affecting performance of finish. Correct conditions detrimental to timely and proper work. Do not proceed until unsatisfactory conditions are corrected.
- B. Verify that base slab meet finish and surface profile requirements in Division 3 Section “Cast-In-Place Concrete,” and Project Conditions above.
- C. Prior to application, verify that floor surfaces are free of construction laitance.
- D. Concrete must be in place a minimum of 28 days or as directed by the manufacturer before application can begin.



3.02 APPLICATION

- A. Execution of Lythic HardWear Floor with process below.
- B.
 - 1. Screen floor with auto scrubber and water.
 - 2. Clean floor with auto scrubber with red pads and clean water.
 - 3. Apply Lythic Densifier at recommended rate 400 Sq. Ft. per gallon, allow to dry.
 - 4. Apply Lythic XL Densifier at recommended rate of 500 Sq. Ft. per gallon, allow to dry.
 - 5. Clean floor with auto scrubber with stripper pads and clean water.
 - 6. Apply Lythic Protector, allow to dry.
 - 7. Burnish floor with stripper pad after floor is dry.
 - 8. Burnish floor with Hogs Hair pad that generates over 90 degrees of heat
- C. **Sealing and Hardening of Concrete Surface**
 - 1. HardWear Floor process to occur at least 10 days prior to racking and other in-store accessory installation, thus providing a complete, uninhibited concrete slab for application
 - 2. Achieve hardening, dust-proofing, and abrasion resistance of the surface without changing the natural appearance of the concrete, except for the sheen.
 - 3. Finish to within ½” of vertical surfaces where practical.
 - 4. Finish level based on test sample.
- D. **Sealer**
 - 1. Apply “Lythic Protector” on the entire floor as a final finish of the polished concrete. Follow application directions and burnish with hogs hair pad for final sheen.
- E. **Final Protection of HardWear Floor Concrete**
 - 1. Following completion of the final polishing, surface must be covered to protect from other trades. Cover with breathable product, such as kraft paper or thin curing blanket. **DO NOT COVER WITH MASONITE, PLYWOOD OR VISQUINE.**



3.03 WORKMANSHIP AND CLEANING:

- A. The premises shall be kept clean and free of debris at all times.
- B. Remove spatter from adjoining surfaces, as necessary.
- C. Repair damages to surface caused by cleaning operations.
- D. Remove debris from jobsite
 - 1. Dispose of materials in separate, closed containers as provided by the owner, and in accordance with local regulations.

3.04 SPECIFIC QUALIFICATIONS / EXCLUSIONS:

- A. Any unforeseen or hidden conditions requiring repair will be billed at time and materials basis.
- B. Assumption that there is adequate access to electrical and water, and that adequate lighting is provided. 1 Phase, 30 amp service required.
- C. That the floor has not been exposed to the elements. If weather damage has occurred, additional grinding will be at time and materials.
- D. Removal of contamination of the slab by soil, foot prints, drag marks, welding marks, hydraulic fluids, or any other outside contaminant will be at time and materials, and will be performed to the best of ability, but without guarantee of removal.
- E. NOTE: Part of the cleaning and sealing of concrete is a wet process and could damage adjacent surfaces, on the immediate floor area, or even the floor levels below. The applicator will endeavor to tape and protect areas adjacent to their work areas to the best of their abilities, but in no case will they be held liable for water damage that occurs to electrical equipment, ceiling tiles, light fixtures, or other adjacent finishes.
- F. No other trades will be allowed in the area being worked on due to possible safety and floor contamination issues.
- G. The areas to receive HardWear[™]Floor will be delivered to the applicator in clean and swept condition. All equipment and supplies will be removed prior to turning the space over to the applicator. If the applicator is required to clean the space, and/or move other's supplies, staging and equipment, it will be done at time and materials.
- H. If a curing agent establishes a bond barrier and requires removal prior to the application of the densifier/hardener, this will be done at time and material.
- I. PROTECTION OF THE FLOOR IS THE RESPONSIBILITY OF THE OWNER.

3.05 PROTECTION:

- A. Protect finished work until fully cured in accordance with manufacturer's recommendations.
- B. When finished, General Contractor shall protect finished areas from excessive water for a period of 30 days (i.e. standing water).

END OF SPECIFICATION